



SECTION THROUGH BLOCK CAVITY WALL AT JUNCTION WITH  
SOLID GROUND FLOOR

RENDER  
MIX TO BE 1:1:6  
(BS 5262)

CELCON SOLAR  
STANDARD OR HI-SEVEN  
BLOCKWORK

RENDER TO BE STOPPED  
AT DPC USING A  
PROPRIETARY STOP BEAD

DPC

G.L.

CELCON FOUNDATION 4  
OR FOUNDATION 7  
BLOCKWORK

INTERNAL FINISH

CAVITY WALL TIE

CELCON SOLAR  
STANDARD OR HI-SEVEN  
BLOCKWORK

SKIRTING

SCREED  
OVERSITE CONCRETE

INSULATION  
DPM

SAND BINDING

HARDCORE